

4-9

65
R

6100409

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,083

00-00

SE NW NW 1/4 SEC. 27, 08 S, 18 W
4290 feet from S section line
4140 feet from E section line

Operator license# 6569 Lease Eckart well # 1

Operator: Carmen Schmitt, Inc. County Rooks

Address: 14 Circle Drive Well total depth 3431 feet
Beloit, Kansas 67420 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 238 feet

111.51

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Red Tiger Drilling Company License# 5302

Address:

Company to plug at: Hour: Day: Month: Year:

Plugging proposal received from: Jerry Ogle

Company: Red Tiger Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3431 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1350 feet " 25 " Mousehole: sacks

3rd plug @ 775 feet " 100 "

4th plug @ 280 feet " 40 "

5th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 4:45 pm, Day: 9, Month: April, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 215 sx 60/40 Pozmix w/ 6% gel and 2 sx celloflake or flowcel

Remarks: Elevation: 1971 5-17-90 GL, Anhydrite depth: 1347 - feet

Did penetrate Arbuckle, cemented by Allied

I did [] / did not [X] observe the plugging.

David K. Wann P.I.R.T. II (agent)

INVOICED

MAY 22 1990

DATE

INV. NO. 28307

4-9

Sub. S