

6070718

10-4
397
163-21300-0006

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-21300-0006
SE SW SE, SEC. 28, T 8 S, R 18 W/E

TECHNICIAN'S PLUGGING REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 11-8-88
8:1988
CONSERVATION DIVISION
Wichita, Kansas

_____ feet from S section line
_____ feet from E section line

Operator License # 5140

Lease Name Schoenthaler Well # 2

Operator: Frontier Oil Co
Name & Address: 1720 Ks St. Bank Bldg.
Wichita, Ks.

County _____ Rooks _____ 111.02

Well Total Depth 3416 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 228

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Csg Pulling and Allied Cmt License Number _____

Address Chase, Ks. and Plainville, Ks.

Company to plug at: Hour: 9:00AM Day: 4 Month: Oct Year: 19 88

Plugging proposal received from Gerald Pfannenstiel

(company name) Frontier Oil Co (phone) _____

were: 8 5/8" 288' S.P. cwc w/165 sks cement. 4 1/2" casing set at 3416' w/200 sks cement.

Perfs 3326' to 3334'. At bottom sand to 3275' and w/4 sks cement. Shot csg twice at 2630' and 2225'. Recovered 2225'. Proposal 200 sks 60/40 Poz 6% Gel and 20 sks gel.

Spot cement through 4 1/2" casing while pulling casing out of hole. 1. at 13-0' w/11 sks gel and 30 sks cement. 2. at 775' w/120 sks cement. 3. at 325' w/4 sks gel and 40 sks

cement and 10 sks at 40'. Plugging Proposal Received by MJS (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30PM Day: 4 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Poz 6% gel. Spotted cement through

4 1/2" casing while pulling 4 1/2" casing.

1. At 1300' spotted 11 sks gel followed with 30 sks cement.
2. At 775' spotted 120 sks cement
3. At 325' spotted 4 sks gel and 50 sks cement (cmt cir) Returned for an additional 50 sks cement. 4. Filled 8 5/8" S.P. to cellar w/25 sks cement. Total cmt

Remarks: used 225 sks. Cemented by Allied Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-9-88

INV. NO. 22950

Signed Marion J. Schmidt
Marion J. Schmidt (TECHNICIAN)