

6010167

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-163-22408-00-00

NE, SEC. 28, T 8 S, R 18 W

800 feet from N/E section line

1154 feet from W/E section line

Schonthaller  
Lease Name Well # B-1

County Rooks

Well Total Depth 3430 111.48 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 276

TECHNICIAN'S PLUGGING REPORT

Operator License # 7960

Operator: Circle S oil co.

Name & Address Box 71

Zurich Ks.

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger License Number 5302

Address 1720 Ks. St. Bk. Bldg. Wichita Ks.

Company to plug at: Hour: AM Day: 8 Month: 7 Year: 19 84

Plugging proposal received from Mike Wagoner

(company name) Red Tiger (phone) 376 263-1201

were: order 185 cement 50/50 pozmix 6% gel 3% C.C.

1.5x hulls 1.8 5/8 plug 1.5x Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 1970 Anhydrite 1346-81 Arbuckle. No

Dakota 1500 Plugging Proposal Received by Dale F. Balthazor

470-770 (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 8:45 AM Day: 8 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 2350 for 20 mi.

25 5x @ 2350

100 5x @ 770 mixed with 1.5x Flow Seal.

40 5x @ 220 Dumped 1.5x hulls pushed plugs to Ko-

20 5x @ 40

10 5x in Rat Hole.

Remarks: Cementing to Halliburton.

(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

INVOICED

DATE 7-27-84

INV. NO. 2714

AUG 3 1984

Signed Dale F. Balthazor (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 7-16-84

JUL 16 1984

CONSERVATION DIVISION Wichita, Kansas

FORM CP-2/3 Rev. 01-84

July 13/84 7