

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19027-00-01
Spot: NWSESE Sec/Twnshp/Rge: 36-8S-17W
990 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: HRABE Well Number: 1
County: ROOKS Total Vertical Depth: 3440 feet

Operator License No.: 8735
Op Name: CRAWFORD, STEPHEN G. DBA S & M OIL
Address: 1725 250TH AVE.
HAYS, KS 67601

Conductor Pipe: Size feet: 8 1/1.80
Surface Casing: Size 8.625 feet: 224 125 SX CMT
Production: Size 4.5 feet: 3379 200 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/05/2002 3:30 PM
Plug Co. License No.: 3722 Plug Co. Name: CROWN WELL SERVICE INC
Proposal Rcvd. from: STEVE CRAWFORD Company: S&M OIL Phone: (785) 650-4003

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well squeezed with 350 sxs on November 02, 1983, in the Dakota.
FL 150'. WLTD 2970'.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/05/2002 7:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 1275'.
Tied onto and circulated cement with 80 sxs cement and 500# hulls.
POOH. Swaged onto 4 1/2" and pumped to pressure with 45 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Annulus full of cement.

RECEIVED
AUG 08 2002
KCC WICHITA
8/8/02

Remarks: LEASE ALSO KNOWN AS TED HRABE #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 8-8-02

INV. NO. 2003060189

AUG 07 2002

ROSENCRANTZ-BEMIS

#1 HRABE

36-8-17W
NW SE SE

Contr. ROSENCRANTZ-BEMIS

ROOKS County

E1951 RB Comm.

Comp. 10-27-61

IP 26 BOPD/LANS

Tops	Depth	Datum
ANH	1250	+701
HEEB	3047	-1096
TOR	3068	-1117
LANS	3089	-1138
ARB	3390	-1439
TD	3440	-1489

Casing OWWO; ORIG COMP AS D & A BY
8" 22# ARTNELL & LEBEN, 5-3-57

SEE OLD CARD FOR DST'S

NEW INFORMATION

WASHED DOWN & CO 3366; 4" 3360; CO 3335
12/3060-63; 8/3090-92; 12/3146-49; 12/
3229-32; 12/3252-55; 12/3267-70; 16/
3274-78; 12/3296-99; SWB 5 BOPH & 2 BWP
/12 HRS; ACID; SWB LD & 11 BOPH & 2
BWP/12 HRS

HRABE POOL OPENER

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS