

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-30326-00-01

LEASE NAME Thyfault

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Hallwood Petroleum, Inc.

SEC. 6 TWP. 8S RGE. 20 (E) or (W)

ADDRESS P.O. Box 378111, Denver, CO 80237

COUNTY Rooks

PHONE# (303) 850-7373 OPERATORS LICENSE NO. 3613

Date Well Completed 10/66

Character of Well Oil

Plugging Commenced 8-15-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-15-91

The plugging proposal was approved on \_\_\_\_\_ (date)

by \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle / Conglom Depth to Top 3428' Bottom 3471' T.D. 3514'

Show depth and thickness of all water, oil and gas formations.

**RECEIVED**  
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled
Arbuckle		Surf.	205	8 5/8"	205'	DEC 30 1991
		Surf	3750	5 1/2"	3514'	12/30/91

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set 8 5/8" set at 205' w/1150 sks, 5 1/2" set at 3514' w/125 sks. Top perf at 3428'. Ran 2 3/8 tbg to 1800' pmp 25 sks 60/40 poz cmt. Pulled tbg to 900' pmp 85' sks 60/40 poz cmt to surf. Pull tbg hook into 5 1/2" csg pmp 140 sks 60/40 poz cmt w/hulls. Hook up to 8 5/8" csg pmp 100 sks 60/40 poz between 8 5/8" by 5 1/2" annulus at 500 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P.O. Box 579, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss.

Audrey L. Marciano (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Donna R. Saune

(Address) Aurora CO

SUBSCRIBED AND SWORN TO before me this 10 day of Oct, 19 91

DONNA R SAUNE  
Notary Public

My Commission Expires: 8-25-92