

15-163-00014-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail: Deliver Report to:  
Conservation Division  
State Corporation Commission  
101 N. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 7 Twp. 8S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines NE SE NE

Lease Owner Graybol Oil Corporation

Lease Name Hamel Well No. 1

Office Address 2200 N. B. T. Bldg., Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 31 1962

Application for plugging filed June 5 1962

Application for plugging approved June 1 1962


Plugging commenced June 1 1962

Plugging completed June 1 1962

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation None Depth to top Bottom Total Depth of Well 3550 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION    | CONTENT    | FROM | TO   | SIZE   | PUT IN | PULLED OUT |
|--------------|------------|------|------|--------|--------|------------|
| Lansing      | Salt Water | 3190 | 3400 | 8 5/8" | 180'   | None       |
| Conglomerate | Salt Water | 3440 | 3486 |        |        |            |
| Arbuckle     | Salt Water | 3486 | 3550 |        |        |            |
|              |            |      |      |        |        |            |
|              |            |      |      |        |        |            |
|              |            |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud-laden fluid. Pumped 125 sacks posmix cement in top of surface casing.

RECEIVED  
JUN 12 1962  
CONSERVATION DIVISION  
Wichita, Kansas

6-12-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graybol Oil Corporation

Address 2200 National Bank of Tulsa Building, Tulsa, Oklahoma

STATE OF OKLAHOMA, COUNTY OF Tulsa, ss.

Lyman C. Dennis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lyman C. Dennis

Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of June 62

Jan Lawrence (Signature)

Notary Public.

My commission expires October 8, 1962



15-163-00014-00-00

GRAYBOL OIL CORPORATION

Rooks County, Kansas

No. 1 Hamel NE SE NE

Section 7-83-20W

Contractor: Company Tools

Elev: K. B. 1954' G.L. 1948'

Commenced: May 22, 1962

Completed: June 1, 1962

Production: Dry

CASING RECORD

180' 8 5/8" Cemented with 180 sacks.

| <u>Depth</u> | <u>Formation</u>    |
|--------------|---------------------|
| 0-180        | Surface             |
| 180-515      | Shale               |
| 515-790      | Shale and Lime      |
| 790-1225     | Sand and Shale      |
| 1225-1380    | Shale and Shells    |
| 1380-1490    | Sand and Shale      |
| 1450-1500    | Anhydrite           |
| 1500-1755    | Anhydrite and Shale |
| 1755-1940    | Shale and Shells    |
| 1940-1960    | Sand and Shale      |
| 1960-2018    | Shale and Shells    |
| 2018-2318    | Shale and Lime      |
| 2318-2420    | Lime and Shale      |
| 2420-2850    | Shale and Lime      |
| 2850-2876    | Lime                |
| 2876-2915    | Shale and Lime      |
| 2915-3085    | Lime and Shale      |
| 3085-3105    | Shale and Lime      |
| 3105-3111    | Lime                |
| 3111-3151    | Shale and lime      |
| 3151-3256    | Lime and Shale      |
| 3256-3395    | Lime                |
| 3395-3431    | Shale and Lime      |
| 3431-3530    | Conglomerate        |
| 3530-3544    | Arbuckle            |

Drillers T. D. 3544

Well T. D. 3550

I hereby certify that the above is a true and correct log of the above captioned well as taken directly from the daily drilling reports.

GRAYBOL OIL CORPORATION

By Edward Haddad  
Edward Haddad, Geologist

STATE OF OKLAHOMA )  
COUNTY OF TULSA }

Subscribed and sworn to before me this 11th day of June, 1962.

My commission expires October 8, 1962

Joe Lawrence  
NOTARY PUBLIC

6-12-62  
RECEIVED  
JUN 12 1962  
CONSERVATION DIVISION