

15-163-00004-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Rooks County. Sec. 13 Twp. 8S Rge. 20 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner Lowell-Voltz, Inc. et al
Lease Name Radke Well No. 1
Office Address 1st Nat'l. Bank Bldg., Colorado Springs, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 30 19 47
Application for plugging filed October 30 19 47
Application for plugging approved October 30 19 47
Plugging commenced October 30 19 47
Plugging completed October 30 19 47
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes - oral.

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top 3486 Bottom Total Depth of Well 3524 Feet

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0'	184'	8 5/8"	184'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with heavy mud to 184' of surface, plugged with 15 sacks cement; filled with heavy mud to cellar and plugged with 10 sacks cement.



(If additional description is necessary, use BACK of this sheet)

11-8-47

Correspondence regarding this well should be addressed to Lowell-Voltz, Inc.
Address 1st National Bank Bldg., Colorado Springs, Colorado

STATE OF Colorado, COUNTY OF El Paso, ss.

Emil E. Bowers (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers

1st Nat'l. Bank Bldg., Colo. Springs, Colo.
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1947

My commission expires

Sept 27, 1949

Notary Public

PLUGGING
FILE SEC 13 T 8 R 200
BOOK PAGE 144 LINE 28

LOG

LOWELL-VOLTZ, INC., ET AL

RADKE #1

SW SW NE SECTION 13-8S-20W

ROOKS COUNTY, KANSAS

Commenced: Oct. 15, 1947
 Completed: Oct. 29, 1947

Surface	0	185
Shale & Shells	185	369
Shale & Sand Streaks	369	1185
Shale & Lime	1185	1303
Red Bed	1303	1355
Shale, Red Bed & Shells	1355	1520
Anhydrite	1520	1560
Shale	1560	1660
Shale & Shells	1660	1865
Salt, Shale & Shells	1865	1960
Shale & Shells	1960	2040
Lime & Shale	2040	2780
Shale & Shells	2780	2805
Shale & Lime Streaks	2805	2880
Lime & Shale	2880	2990
Lime	2990	3007
Lime & Shale	3007	3098
Lime	3098	3128
Lime & Shale Streaks	3128	3195
Lime & Shale	3195	3242
Lime - K.C.	3242	3273
Lime, soft	3273	3276
Lime	3276	3322
Lime, Cherty	3322	3389
Lime	3389	3499
Lime, Arb.	3499	3524
Total Depth	3524	

CASING RECORD

8 5/8" casing set at 184'
 and cemented with 125 sacks
 of Red Star cement.

STATE OF COLORADO)
) ss
 COUNTY OF EL PASO)

NOV-8-1947
 11-8-47

I hereby affirm that the above and foregoing
 is a true and correct copy of the log of Lowell-Voltz, Inc., et al-
 Radke #1 well, located in the C SW NE of Section 13-8S-20W, Rooks
 County, Kansas.

PLUGGING
 FILE SEC 13 T 8 R 20W
 BOOK PAGE 144 LINE 28

LOWELL-VOLTZ, INC.

By J. R. Lawrence
 President

Subscribed and sworn to before me, a Notary Public, this 5th day
 of November, 1947.

W. E. Doyle
 Notary Public

My commission expires:

Sept 27, 1949