


15-163-20285-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 22 Twp. 8S Rge. (E)20 (W) _____
Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner I. O. Miller

Lease Name Balthazor Well No. 1

Office Address 619 Brown Bldg., Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Jan. 5, 19 70

Application for plugging filed Jan. 5, 19 70

Application for plugging approved Jan. 5, 19 70

Plugging commenced Jan. 5, 19 70

Plugging completed Jan. 5, 19 70

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3580 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	217'	8-5/8"	217'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 600 feet. Set first plug at 600 feet with 70 sacks cement. Filled hole with heavy mud to 210 feet. Set second plug at 210 feet with 20 sacks cement. Filled hole with heavy mud to 40 feet. Set third plug at 40 feet with 10 sacks cement. Job complete at 11:30 AM, Jan. 5, 1970. Cement pumped through drill pipe with Globe Cement pump truck.

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1970
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc. 1-12-70
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall

830 Sutton Place, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 8 day of January, 19 70



Barbara J. Layton
Barbara J. Layton Notary Public.

15-163-20285-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

1-12-70
RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1970
CONSERVATION DIVISION
Wichita, Kansas

BALTHAZOR #1
NW SE Section 22-8S-20W
Rooks County, Kansas

Commenced: December 29, 1969
Completed: January 5, 1970

OPERATOR - I. O. Miller

DEPTH		FORMATION	REMARKS
From	To		
0	144	Top soil, shale and rock	
144	150	Lime	
150	218	Shale	Ran 6 joints 8-5/8" casing, set @ 217' w/150 sacks cement.
218	560	Shale	
560	720	Shale and sand	
720	830	Sand	
830	1310	Shale	
1310	1546	Shale and red bed	
1546	1581	Anhydrite	
1581	2605	Lime and shale	
2605	2745	Lime	
2745	3170	Lime and shale	
3170	3254	Lime	
3254	3342	Lime and shale	
3342	3468	Lime	
3468	3495	Conglomerate	
3495	3580	Lime	
3580	TD		Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NW SE Section 22-8S-20W, Rooks County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 8 day of January, 1970, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

