

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-163-21,642 *00-00*

LEASE NAME Goosling B-1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE NE NE

SEC. 22 TWP. 8s RGE. 20w(E) or (W)

COUNTY Rooks

Date Well Completed \_\_\_\_\_

Plugging Commenced 11/12/85

Plugging Completed 11/21/85

**TYPE OR PRINT**

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kelso Casing bought f/ Andrew Goosling

ADDRESS Box 347, Chase, Ks. 67524

PHONE # (316) 938-2457 OPERATORS LICENSE NO. 6050

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3840'

Show depth and thickness of all water, oil and gas formations.

**OIL, GAS OR WATER RECORDS**

**CASING RECORD**

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	223'	none
				5 1/2"	3838'	1700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with 5 sacks cement, sand to 3400' & 5 sacks cement. Shot pipe @ 2535' 2115', 1898' & 1700'. Pulled 40 joints of pipe. Plugged well with 5 hulls, 5 gel, 50 cement, 15 gel, 100 cement, 10 gel, 8 5/8 plug, & 50 sacks 60/40 poz 6% gel 3% c.c.  
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 1985

My Commission expires: \_\_\_\_\_



[Signature]  
Notary Public

NOV 25 1985  
11-25-85