

LEASE NAME Baldwin

WELL NUMBER 1

2970 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 8S RGE. 20 ~~XXXXX~~ (W)

COUNTY Rooks

Date Well Completed 4-11-89

Plugging Commenced 4-12-89

Plugging Completed 4-12-89

LEASE OPERATOR Thunderbird Drilling, Inc.

ADDRESS P. O. Box 780407, Wichita, KS 67278

PHONE# (316) 685-1441 OPERATORS LICENSE NO. 5131

Character of well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-12-89 (date)

by State Pluggger, Gilbert Schenk (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	249'	None

4-24-89
RECEIVED
STATE CORPORATION COMMISSION
APR 24 1989
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the cement or other fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Circulate heavy mud in hole. 1st plug from 1550' to 1470' w/20 sx. 2nd plug from 850' to 450' w/100 sx & 1 sack Flo Seal. 3rd plug from 300' to 140' w/40 sx. 4th plug from 40' to surface. Rathole-10 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thunderbird Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton
150 N. Main, Suite 801
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 19th day of April, 19 89

Janet A. Stuck
Notary Public

Commission Expires: 12-29-90

