


15-163-00451-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Rooks County. Sec. 25 Twp. 8 Rge. 20 (E) W (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE SW  
Lease Owner B & R Drilling, Inc.  
Lease Name Whismand Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7/23/52 19  
Application for plugging filed 7/22/52 19  
Application for plugging approved 7/22/52 19  
Plugging commenced 7/23/52 19  
Plugging completed 7/23/52 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3575 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	193	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUGGING RECORD

Filled hole with heavy mud to 180', set first plug, mixed and poured 15 sacks cement through drill pipe. Filled hole with mud to 40', set second plug, 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. A. Michaelis, Jr.*  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 52

My commission expires 6-17-54.

24-2675-S 2-52-20M

PL  
FILE SEC 25 8 200  
BOOK PAGE 33 LINE 1

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 5 1952 8-5-52  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-00451-00-00

B & H Drilling, Inc.  
Whisman No. 1

NE NE SW 25-8-20N  
Rooks County, Kansas

Total Depth: 3575'  
Comm. 7/4/52  
Comp. 7/23/52

Casing

8 5/8" Set 193'

Cement

130 sacks Portland

Formation

Depth

Surface soil-sand-shale	95
Sand-shale	150
Shale-shells	625
Shale-sand	720
Shale-sand-shells	1465
Anhydrite	1605
Shale-shells	1775
Shale	1975
Shale-lime	3283
Lime	3575'

STATE OF KANSAS }  
                          } SS  
RUSSELL COUNTY }

I hereby certify that the above information is true and correct to the best of my knowledge.

Caro Betz

Subscribed and sworn to before me this 4th day of August, 1952.

Wm. Thomas  
Notary Public

My commission expires: 6-17-54.

RECEIVED  
CORPORATION COPY SECTION

AUG 5 1952

RECREATION DIVISION  
Wichita, Kansas

8-5-52

FILE SEC 25 P. 100  
BOOK PAGE 33