

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-23,178 00-00

LEASE NAME Bouchey

WELL NUMBER #1

1650' FSI Ft. from S Section Line

1650' FEI Ft. from E Section Line

SEC. 26 TWP. 8S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed _____

Plugging Commenced 8-27-91

Plugging Completed 8-27-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hellar Drilling Co., Inc.

ADDRESS 125 N. Market, Suite 1422, Wichita, KS 67202

PHONE#(316) 267-2845 OPERATORS LICENSE NO. 5015

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 27, 1991 (date)

by Gib Scheck (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3631'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	263'	None

10-1-91
RECEIVED

STATE CORPORATION COMMISSION
OCT 01 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill w/heavy mud; set 1st plug @ 3600'-3500' w/25 sx; 2nd plug @ 1600'-1500' w/25 sx; 3rd plug @ 900'-500' w/100 sx & 1 sx Floccel; 4th plug @ 300'-140' w/40 sx; 5th plug @ 40'-surface w/wiper plug w/10 sx; rathole 15 sx; Total 215 sx 60-40 premix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hellar Drilling Co., Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 30th day of September, 19 91

Angela Woodard
Notary Public

My Commission Expires: March 20, 1993