

15-163-00772-08-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 27 Twp. 8 Rge. 20 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SW SE NW/4

Lease Owner I. O. Miller

Lease Name Miller - Fee Well No. 1

Office Address P.O. Box 274 - Ellis, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) DH

Date well completed 11-4-58 19

Application for plugging filed 11-4-58 19

Application for plugging approved 11-4-58 19

Plugging commenced 11-5-58 19

Plugging completed 11-5-58 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Eldon Petty)

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3562 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	232	8 5/8	236.60	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 550 ft - set plug w/ 20 sx cement thru drill pipe
Mudded to 210 ft - set plug w/ 15 sx cement
Mudded to 40 ft - set plug w/ 10 sx cement 1/4 sx hulls

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Virginia Drilling Co Inc.
Address 712 Brown Bldg- Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
S. A. Murphy (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Murphy
712 Brown Bldg- Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 19 58,

My commission expires Febr. 5, 1961. Notary Public.

PLUGGING
FILE SEC 27 T. 8 R. 20W
BOOK PAGE 146 LINE 2

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1958
CONSERVATION DIVISION
Wichita, Kansas

15-163 00772-00-00

Miller # 1 Fee - SW SE NW/4 Sec. 27-8-20 Rooks County, Kansas
Company - I. O. Miller
Contractor - Virginia Drlg. Co Inc.
Commenced - October 23, 1958
Completed - November 5, 1958
Elevation - 2012 RB
Total Depth - 3562

8 5/8" set at 232 w/145 sz cem.
2 1/2 cc
Dry Hole.

FORMATION	DEPTH	TOPS:
Sand - soil	0 - 20	
Sand - shale	20 - 200	
Shale	200 - 560	2963 - Howard
Sand-shale	560 - 640	3002 - Topeka
Shale	640 - 745	3192 - Heebner
Shale-redbed	745 - 1010	3210 - Toronto
Sand	1010 - 1250	3228 - Lansing KC
Shale-shells	1250 - 1490	3447 Base KC
Anhydrite	1490 - 1505	3501 - Cong.
Shale-shells	1505 - 1885	3506 - Shaley Arb.
Shale -lime	1885 - 2614	3544 - Solid Arb.
Lime	2614 - 2648	
Lime-shale	2648 - 2970	
Lime	2970 - 3562 T D	

D. A. Murphy

Subscribed and sworn to before me, a Notary Public,
this 13th day of November, 1958.

M. H. Hartman
Notary Public

My commission expires: Feb. 5, 1961

RECEIVED
STATE CORPORATION COMMISSION

11/15/58

NOV 15 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC. 27 T 8 ROW	
BOOK PAGE 146	LINE 2