

15-065-00250-00-01


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County, Sec. 21 Twp. 8S Rge. 21W (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE  
Lease Owner Glickman Oil Company, Et Al  
Lease Name Newell Well No. 1  
Office Address 439 S. St. Francis, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 13, 1951 19  
Application for plugging filed August 12, 1951 (verbal) 19  
Application for plugging approved August 15, 1951 19  
Plugging commenced August 13, 1951 19  
Plugging completed August 13, 1951 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production none 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3686 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	194	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

This well opened for second time for  
drill stem test by Johnston Field Service  
Plainville, Kansas and plugged for the second  
time by Smitherman & Cohen Drilling Company  
Circulated hole with heavy rotary mud;  
pushed cementing plug to 175 feet. displaced  
15 sacks of cement through drill pipe. Filled  
with rotary mud to 40 feet. Set cementing plug  
1/2 sack of hulls and 10 sacks of cement filling  
to bottom of cellar.

This well was first plugged on August 8, 1951.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Smitherman & Cohen Drilling Co.,  
Address P. O. Box 692,  
El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
L. C. Smitherman (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P. O. Box 692 El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of September, 1951

My commission expires March 3, 1955 [Signature] Notary Public.

23-8390-s 6-51-20M

PLUGGING  
FILE SEC 21 T 8 R 21W  
BOOK PAGE 108 LINE 45