

15-065-02252-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
off formations.

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 21 Twp. 8S Rge. 21W (E) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE NE NE  
Lease Owner. Anderson-Prichard Oil Corporation  
Lease Name. Brault Well No. 1  
Office Address. Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole). Dry hole  
Date well completed. November 14, 19. 47  
Application for plugging filed. (Verbal) November 14, 19. 47  
Application for plugging approved. (Verbal) November 14, 19. 47  
Plugging commenced. November 14, 19. 47  
Plugging completed. November 14, 19. 47  
Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production. 19.  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3670 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 10-3/4 | 224    | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 223'.  
Set bridging plug at 223' and plugged  
with 20 sacks of cement through drill  
pipe. Filled with heavy mud to 10'.  
Set bridging plug at 10' and plugged  
with 15 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Anderson-Prichard Oil Corporation  
Address. Oklahoma City, Oklahoma

STATE OF Kansas COUNTY OF Segwick, ss.  
M. W. Smith (employee of owner) or ~~owner~~ of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *M. W. Smith*  
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of November 19. 47.

My commission expires January 21, 1950.

*Patricia Meeker*  
Patricia Meeker Notary Public.

PLUGGING  
FILE SEC 21 T 8 R 21 W  
BOOK PAGE 147 LINE 25

11-18-47

15-065-02252-00-00

DRILLER'S LOG OF FORMATIONS  
ENCOUNTERED IN  
ANDERSON-PRICHARD OIL CORPORATION  
ALEXINA BRAULT #1  
C-SE/4 NE/4 NE/4 Sec. 21-6S-21W  
GRAHAM COUNTY, KANSAS

| FORMATIONS           | FROM       | TO   |                    |
|----------------------|------------|------|--------------------|
| Clay, Shale & Shells | 0          | 224  | Run 22 3/4 10-3/4" |
| Shale & Shells       | 224        | 1095 | Spiral Weld Casing |
| Sand                 | 1095       | 1300 |                    |
| Shale & Shells       | 1300       | 1590 |                    |
| Anhydrite            | 1590       | 1620 |                    |
| Shale & Shells       | 1620       | 1720 |                    |
| Lime                 | 1720       | 1925 |                    |
| Shale & Shells       | 1925       | 2015 |                    |
| Lime                 | 2015       | 2050 |                    |
| Broken Lime          | 2050       | 2255 |                    |
| Shale & Lime         | 2255       | 2390 |                    |
| Broken Lime          | 2390       | 2530 |                    |
| Shale & Lime         | 2530       | 2685 |                    |
| Lime                 | 2685       | 2820 |                    |
| Shale & Lime         | 2820       | 2995 |                    |
| Lime                 | 2995       | 3056 |                    |
| Broken Lime          | 3056       | 3074 |                    |
| Lime                 | 3074       | 3085 |                    |
| Lime & Shale         | 3085       | 3272 |                    |
| Lime                 | 3272       | 3310 |                    |
| Lime & Shale         | 3310       | 3395 |                    |
| Lime                 | 3395       | 3497 |                    |
| Lime, Shale & Chert  | 3497       | 3535 |                    |
| Shale & Shells       | 3535       | 3552 |                    |
| Lime                 | 3552       | 3585 |                    |
| Shale                | 3585       | 3620 |                    |
| Lime                 | 3620       | 3670 |                    |
|                      | TD D. & A. | 3670 |                    |

112047  
NOV 20 1947

Contractor - Transit Corporation  
Apo Tower  
Oklahoma City, Okla.

PLUGGING  
NOV 20 1947

I hereby certify the foregoing to be a true and correct  
driller's log of the formations encountered in the above well.

*Victor E. Davis*  
Assistant Secretary

Certified to before me this 18th day of November, 1947  
*Ernest James Scott*  
Notary Public

My Commission Expires Mar. 7, 1951

DATE STARTED November 3, 1947

COMPLETED November 11, 1947