


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-065-00688-0000
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 22 Twp. 8S Rge. 21W (#/ (W)
Location as "NE/CNW/SW" or footage from lines NW/NW/SE
Lease Owner Forbes Casing Pulling Co.
Lease Name Newell "A" Well No. #1
Office Address Box 221, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____
Application for plugging filed Yes 19____
Application for plugging approved Yes 19____
Plugging commenced _____ 6-12- 19 58
Plugging completed _____ 6-20 19 58
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A.D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | | |
| | | | | 5 1/2" | | 2,933' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3640'.
Plugging started 6-12-58. Finished 6-20-58.
Plugged off bottom with sand to 3620' and dumped 4 sacks cement.
Worked and shot pipe. Shot 5 1/2" casing at 2,933'. Pulled pipe out of hole. Plugged well as follows: Mudded to 235'. Set rock bridge and dumped 25 sacks cement. Filled hole with mud to 40'. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co. 6-22-58
Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J.O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of July, 1958

My commission expires November 8, 1960. Petty S. Edman Notary Public.

PLUGGING
FILE SEC 22 T. 8 R 21W
BOOK PAGE 104 LINE 20

Scharnhorn Oil Corporation
 Nowell A #1
 NW-NW-SE, Sec. 22 - 8S -21W
 Graham County, Kansas

15-065-00688-00-00

Drillers Log

Drilling started 8-10-55
 Drilling Ended 8-22-55
 8 5/8" casing set @ 239'

| From | To | Formation | Remarks |
|------|------|-------------------|---|
| 0 | 239 | Shale | Ran 245' of 8 5/8" casing set at 239' with 225 sacks cement |
| 239 | 900 | Shale-Shells-Sand | |
| 900 | 1090 | Red-Bed - Shale | |
| 1090 | 1300 | Sand | |
| 1300 | 1560 | Shale - Sand | |
| 1560 | 1565 | Shale & Shells | |
| 1565 | 1590 | Anhydrite | |
| 1590 | 1715 | Shale | |
| 1715 | 2150 | Shale - Lime | |
| 2150 | 2610 | Lime - Shale | |
| 2610 | 2705 | Lime | |
| 2705 | 3016 | Shale - Lime | |
| 3016 | 3265 | Lime - Shale | |
| 3265 | 3480 | Lime | |
| 3480 | 3586 | Lime & Shale | |
| 3586 | 3640 | Arbuckle | T.D. - Ran 118 Jts. 5 1/2" casing |

This is a certified copy of the Drillers Log as shown by the Daily Drilling Reports.

Richard E. ...
 Madger Drillers, Inc.

Subscribed and sworn to before me this 13th day of September, 1955.

Margaret Walsh
 Notary Public

My Commission expires 7-6-59

6-2-58

PLUGGING
 SEC. 22 T. 8 S. 21W
 BOOK PAGE 104 20