

15-005-21467-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Graham SEC. 22 TWP. 8 RGE. 21  W  
 Location as in quarters or footage from lines:

SE 1/4 SW SW


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner H & H Exploration  
 Lease Name Hamel Well No. 1  
 Office Address Box 96, Plainville, KS 67663  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry hole  
 Date Well Completed 1-10-82  
 Application for plugging filed 1-10-82  
 Plugging commenced 1-10-82  
 Plugging completed 1-10-82  
 Reason for abandonment of well or producing formation Dry hole

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Formation	Content	From	To	Size	Casing Record	
					Put in	Pulled Out
				8-5/8"	228'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud laden fluid @ 3685' - 840'  
70 sks cement @ 840'  
40 sks cement @ 240'  
10 sks cement @ 40'  
10 sks cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.


Joe K. Branum (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum  
P.O. Box 506, Russell, KS 67665  
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 19 82

My Commission expires: April 29, 1984.

Joyce Ann Ridgley  
 Notary Public.



RECO  
 1-13-82

15-065-21467-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665

DRILLERS LOG

OPERATOR: H & H Exploration  
P. O. Box 96  
Plainville, Kansas 67663

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665

LEASE: Hamel WELL: #1

LOCATION: <sup>SE</sup> SW SW SW  
Section 22-8S-21W  
Graham County, Kansas

Total Depth: 3685'

Elevation:

Commenced: 12-31-81

Completed: 1-10-82

Casing: 8-5/8" @ 228' with 170 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top soil & sand	30'	Shale & lime	2820'
Sand & shale	816'	Shale	2980'
Shale	1125'	Shale & lime	3364'
Sand	1355'	Lime	3505'
Shale	1630'	Lime & shale	3517'
Anhydrite	1665'	Lime	3680'
Sand & shale	2585'	Lime & shale (R.T.D.)	3685'

RECEIVED  
STATE CORPORATION COMMISSION

JAN 13 1982

CONSERVATION DIVISION

Wichita, Kansas

1-13-82

STATE OF KANSAS )

ss:

COUNTY OF RUSSELL )

I, Joe K. Branum, of Emphasis Oil Operations, state that the above and foregoing is a true and correct log of the above captioned well.

*Joe K. Branum*  
Joe K. Branum

Subscribed and sworn to before me this 12th day of January, 1982.

My Commission Expires: April 29, 1984.

NOTARY PUBLIC  
JOYCE ANN RIDGLEY  
Russell County, Kansas  
My Appt. Exp. 4-29-84

*Joyce Ann Ridgley*  
Notary Public