


15-069-00418-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building 211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

GRAHAM County. Sec. 31 Twp. 8 Rge. 21 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SE SW
Lease Owner COOPERATIVE REFINERY ASSOCIATION
Lease Name ANDREGG "A" Well No. 1
Office Address Box 765 GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed September 18 1954
Application for plugging filed September 18 1954
Application for plugging approved September 18 1954
Plugging commenced September 18 1954
Plugging completed September 22 1954
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3730 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3730 feet to TOP feet for each plug set.

HOLE FILLED WITH SAND FROM 3730 TO 3680; four SACKS OF CEMENT DUMPED IN HOLE WITH DUMP BAITER TO FORM CEMENT PLUG BETWEEN 3680 AND 3618.
HOLE FILLED WITH MUD FROM 3618 TO 215'. ROCK BRIDGE INSTALLED BETWEEN 215' and 205'. FIFTEEN SACKS OF CEMENT POURED IN HOLE. HOLE FILLED WITH MUD TO 35'. FIVE FOOT ROCK BRIDGE INSTALLED BETWEEN 35' and 30'.
HOLE CAPPED WITH TEN SACKS OF CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor BARNES & SONS PIPE HULLING COMPANY
Address RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, SS.
CARL A. SELLERS (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl A. Sellers

BOX 765 GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 8th day of OCTOBER, 1954.

My commission expires AUGUST 17, 1957

Notary Public.

PLUGGING
FILE SEC 31 T 8 R
BOOK PAGE 65 LINE 8

10-11-54

15-065-00418-00-00

DRILLERS LOG

Andregg A #1

Loc: NE SE SW
Sec: 31-8-21
Graham County, Kansas
Operator: Cooperative Refinery Assoc.
Contractor: Rig #5

Elevation: 2143' D. F.
Casing: 8 5/8" @ 215' w/150 Sax Posmix
2 Sax. C. C.

5 1/2" @ 3702' w/125 Sax Posmix

Comm: 8-14-54 Comp: 8-24-54
T D 3712'

<u>From</u>	<u>To</u>	<u>Formation</u>
0	215	Surface
215	510	Shale & Shells
510	1140	Shale, Sand & Shells
1140	1670	Shale & Shells
1670	2055	Shale, Shells & Lime
2055	2235	Shale & Shells
2235	3370	Shale & Lime
3370	3373	Lime
3373	3399	Shale & Lime
3399	3434	Lime
3434	3465	Shale, Sand & Lime
3465	3541	Lime
3541	3580	Shale & Lime
3580	3640	Shale, Chert & Lime
3640	3680	Lime
3680	3707	Shale & Lime
3707	3712	Lime
3712		T D

(STATE OF KANSAS)
(COUNTY OF GRAFTON)

I hereby certify that the above is a true and correct copy of the log on the Andregg "A" #1 well, located NE SE SW of Section 31-8-21, Graham County, Kansas.

P. A. Jackson

Subscribed and sworn to before me this 30 Day of August 1954

Donald E. Hunt

My commission expires: August 17, 1957

16-16-54

PLUGGING
FILE SEC 31 T 8 R NE SW
BOOK PAGE 65 LINE 8