

State of Kansas



15-065-20117-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas

2-7-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: Madden-Davis Well No. D-1
B-1

Location: NE-NE-SE Sec. 7 Twp. 8 Rge. (E)(W)25

County Graham Total Depth 3995 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

239'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Dakota section from 1000' to 1200'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP
from 245' to 185'. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10
Sx. cement to bottom of cellar.

Very truly yours,

M. S. Nichols
Conservation Division Agent