



15-065-20321-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1970
CONSERVATION DIVISION
Wichita, Kansas
5-11-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Johnnie Crowe of Garvey Drilling Company, has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Graham County Well No. 1

Location: 440' SNL & 440' WEL-NE Sec. 9 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3952' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

175'---8 5/8" Surface casing, cement circulated with 160 Sx.

Circulate hole with heavy mud. Pull DP to 1075' and displace 100 Sx.

cement thru DP. Pull DP to 185' and displace 25 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent