

State of Kansas



15-065 - 02784-020

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling Co has this date requested permission to plug the following described well:

Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Building, Wichita, Kansas.

Lease Name: Madden-Davis Well No. A-7

Location: CN/2-NW-SW Sec. 16 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3807 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Barnes was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated.

3797'--5 3/4" Production casing cemented.

Sand well back to 3775' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 30 sacks gel plus 5 sacks hulls in initial gel and 130 Sx. cement staged.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Very truly yours,

A. S. Pilsch  
Conservation Division Agent