



15-065-01351-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

5/24/71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Isadore Dreher of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Dreher guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: Box #352, Russell, Kansas.

Lease Name: Waltz <sup>KCC</sup> Waltz <sup>ZAP</sup> Well No. B-1

Location: NE-SW-NE Sec. 25 Twp. 8 Rge. (E)(W) 25

County: Graham Total Depth 3950' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Dreher was instructed to plug the well as follows:

161'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3949'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back indicated. Top perforations @ 3883'.

Push plug to 3800', sand back to 3775' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

Conservation Division Agent