

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,267-00-00

LEASE NAME Riggs

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

1320 Ft. from S Section Line

3630 Ft. from E Section Line

LEASE OPERATOR V & F Oil Company

SEC. 7 TWP. 8 RGE. 21 ~~XXXX~~(W)

ADDRESS P.O. Box 1053, Hays, KS 67601

COUNTY Graham

PHONE#(913) 628-2495 OPERATORS LICENSE NO. 8942

Date Well Completed 11-24-85

Character of Well D & A

Plugging Commenced 11-25-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-25-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes.

Which KCC/KDHE Joint Office did you notify? Hays, KS

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation None Depth to Top _____ Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
1st plug @ 3580' with 25 sacks, 2nd plug @ 1570' with 25 sacks, 3rd plug @ 830' with 100 sacks & 1 sack flo-seal, 4th plug @ 230' with 40 sacks, 5th plug @ 40' with 10 sacks and solid bridge, Rat Hole with 15 sacks & Mouse Hole with 10 sacks. TOTAL: 225 sacks 60/40 Pozmix & 6% Gel.
PLUG DOWN at 12:00 pm 11-25-85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc.

Address Box 342, Plainville, KS 67663

STATE OF Kansas COUNTY OF Sedgwick

Doug Van Loenen

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Doug Van Loenen


(Address) P. O. Box 1053
Hays, Kansas 67601

SUBSCRIBED AND SWORN TO before me this 20th day of December, 19 85

Lucille B. VonFeldt
Notary Public

My Commission Expires: March 25, 1987

12-20-85
RECEIVED N/A
STATE CORPORATION COMMISSION
DEC 20 1985
CONSERVATION DIVISION



CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: November 18, 1985
month day year

API Number IS- 065-22,267

OPERATOR: License # 8942
Name V & F Oil Company
Address P.O. Box 1053
City/State/Zip Hays, Kansas 67601
Contact Person Doug Van Loenen
Phone 913-628-2495

C. W. E. (location) SW/4 Sec 7... Twp 8... S, R40...
1320 Ft North from Southeast Corner of Section
3630 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # *Mohawk 6394*
Name
City/State

Nearest lease or unit boundary line 330' west
County Graham
Lease Name Riggs
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 150 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 900 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 200 feet
Conductor pipe if any required N/A feet
Ground surface elevation Unknown feet
This Authorization Expires 5-5-86
Approved By 11-5-85

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Projected Total Depth 3620 feet
Projected Formation at TD Arbuckle
Expected Producing Formations Kansas City - Arbuckle

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.
Production string, if set, will be cemented thru the Dakota formation.
11/4/85... Signature of Operator or Agent *Doug Van Loenen* Title General Partner

Ed Philbert - Mohawk Drilling
Set 200 ft SP - alt II

P.M. mff

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1985 129-85

CONSERVATION DIVISION

RECEIVED
COUNTY DIST #6
HAYS, KS