

15-065-02692-00-00

WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 15 Twp. 8S Rge. (E) 21(W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. C SW/4 SE/4 SW/4
Lease Owner Bridgeport Oil Company, Inc.
Lease Name Benoit Well No. 1
Office Address 210 Schweiter Building - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10 - 5 19.43
Application for plugging filed 10 - 5 19.43
Application for plugging approved 10 - 5 19.43
Plugging commenced 10 - 5 19.43
Plugging completed 10 - 5 19.43
Reason for abandonment of well or producing formation Non-Productive

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander
Producing formation Depth to top Bottom Total Depth of Well 3637 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	206'	None
					cemented with 125 sacks	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud 3637' to 206'
Set plug at 206' and cemented on top of plug with 15 sacks
Filled hole with mud to 26'
Set plug at 26' and cemented on top of plug with 9 sacks to within 6' of top

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Bridgeport Oil Company, Inc. 10-12-43
Address 210 Schweiter Building - Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Frank Leach (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Leach
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of October, 19 43
My commission expires Dec. 13, 1945
Helen Shore Notary Public.

15-065-02692 00 00

MIDWAY OIL COMPANY, INC.
 210 Schmeiter Building
 Wichita 2, Kansas

Well Log—Benoit #1
 C SW/4 SE/4 SW/4 15-23-21W
 Graham County, Kansas

Casing Record:
 6-3/8" casing cemented @ 226'
 with 125 sacks bulk cement.

Elevation—2370
 Date started—7/19/43
 Date Completed—10/5/43

Rotary Tools—0 to 3637

LOG	
0	50 Surface
50	200 Sand, Clay & Shale
200	250 Shale Blue
250	360 Shale & Lime Shells
360	610 Shale & Shells
610	930 Sand & Shells
930	1085 Shale, Shells & Sand
1085	1560 Sand
1560	1620 Shale & Lime
1620	1640 Anhydrite
1640	1645 Lime & Shale
1645	1870 Shale & Shells
1870	1980 Shale & Lime Shells
1980	2014 Shale & Sand
2014	2200 Lime & Shale
2200	2279 Shale & Lime Shells
2279	2425 Lime & Shale
2425	2535 Shale & Lime Shells
2535	2620 Lime & Shale
2620	2700 Shale & Lime Shells
2700	2912 Lime & Shale
2912	2990 Lime
2990	3110 Shale & Lime
3110	3253 Lime
3253	3269 Shale & Lime
3269	3307 Lime
3307	3355 Lime & Shale
3355	3456 Lime
3456	3540 Shale & Lime
3540	3600 Shale
3600	3607 Lime
3607	3637 Dolomite
3637	

Plugged and Abandoned 10/5/43

CORRELATION TOPS	
Top Anhydrite	1620
Top Topoka	3010
Top Hochstet	3217
Top Toronto	3267
Base Grand	3280
Top Lansing	3285
Base K.C.	3490
Top Conglomerate	3575
Top Arbuckle	3600

I, Frank Leach, do hereby certify that the above log is correct to the best of my knowledge and belief.

MIDWAY OIL COMPANY, INC.
Frank Leach

10-12-43

PLUGGING
 FILE 15 8 21W
 BOOK PAGE 93 OF 40