

15-065-21687-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 15 TWP. 8S RGE. 21 E/W
 Location as in quarters or footage from lines:
NE SW NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner High Plains Oil Explorations, Inc.
 Lease Name Gosselin Well No. 1
 Office Address 8575 W. 110th St., Suite 105, Overland Park, KS 66210
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 10-15-82
 Application for plugging filed 10-15-82
 Plugging commenced 10-15-82
 Plugging completed 10-16-82
 Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3615'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	254'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Mud laden fluid @ 3600' - 3615'
 20 sks cement @ 3600'
 20 sks cement @ 1554'
 80 sks cement @ 800'
 10 sks cement @ 40'
 10 sks cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Joe K. Branum
 P. O. Box 506, Russell, KS 67665
 (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1982



Glenda R. Tiffin
 Glenda R. Tiffin, Notary Public.
 STATE CORPORATION COMMISSION

My Commission expires: February 6, 1984.

OCT 27 1982
 CONSERVATION DIVISION
 Wichita, Kansas
 10-27-82

RECEIVED
STATE CORPORATION COMMISSION

15-065-21687-00-00

OCT 27 1982

EMPHASIS OIL OPERATIONS

P. O. Box 506

CONSERVATION DIVISION
Wichita Kansas

Russell, Kansas 67665

10-27-82

DRILLERS LOG

OPERATOR: High Plains Oil Explorations, Inc.
8575 W. 110th St., Suite 105
Overland Park, Kansas 66210

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665

LEASE: Gosselin WELL: #1

LOCATION: NE SW NW
Section 15-8S-21W
Graham County, Kansas

Total Depth: 3615'

Elevation:

Commenced: 10-9-82

Completed: 10-16-82

Casing: 8-5/8" @ 254' with 150 sks cement

Status: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Topsoil & Sand	30'	Shale & Lime	3215'
Clay, Sand & Shale	260'	Lime	3323'
Shale & Sand	1550'	Lime & Shale	3426'
Shale & Lime	1553'	Lime	3480'
Anhydrite	1589'	Lime & Shale (R.T.D.)	3615'

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.



Joe K. Branum

Subscribed and sworn to before me this 25th day of October, 1982.

My Commission Expires: February 6, 1984.





Notary Public