


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-00151-06-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 19 Twp. 8S Rge. 21W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$  SW $\frac{1}{4}$  SW $\frac{1}{4}$   
Lease Owner Kantor Oil Co. et al  
Lease Name Jellison Well No. 1  
Office Address P. O. Box 846, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 10-25- 1950  
Application for plugging filed 10-25- 1950  
Application for plugging approved 10-25- 1950  
Plugging commenced 10-25 1950  
Plugging completed 10-25- 1950  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation none Depth to top          Bottom          Total Depth of Well 3696 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	156'	8-5/8" 2 1/2"		none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet for each plug set.

Plugged hole with 20 sacks cement on plug at 250 feet;  
10 sacks cement on top plug.


(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Kantor Oil Company  
Address P. O. Box 846, Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK

Richard Hindery, partner of Birmingham-Bartlett Drilling Co. of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard Hindery



SUBSCRIBED AND SWORN to before me this 26th day of October 1950

Vivian J. Winger  
Notary Public.

My commission expires November 29, 1950.

22-7877-s 4-49-10M  
PLUGGING  
FILE SEC 19T 8 R 2W  
BOOK PAGE 39 LINE 5

1028-50

15-005-00151-00-00

JELLISON #1 WELL

LOCATION: SW $\frac{1}{4}$  SW $\frac{1}{4}$  SW $\frac{1}{4}$  Sec. 19-8S-21W  
Graham County, Kansas

OPERATOR: Kantor Oil Company

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE: Ran 5 jts., 159.94' of 8-5/8" 24# casing cemented @ 156 ft. with 125 sacks cement and 1 c.c.

OIL STRING: None. D & A.

SPUNDED: 10-16-50

COMPLETED: 10-25-50

100

(Figures indicate bottom of formation)

0 to 156	Surface
1145	Shale
1440	Sand
1626	Shale and Red Bed
1658	Anhydrite
2410	Shale
2810	Shale and lime
3137	Shale
3320	Lime and shale
3585	Lime
3618	Conglomerate
3645	Shale and conglomerate
3666	Conglomerate
3696	Arbuckle
3696	Total Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Jellison No. 1 well as shown on the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

BY Richard Hindery

Subscribed and sworn before me  
this 26th day of October, 1950.

Vivian J. Ginger  
Notary Public

My commission expires November 29, 1950.

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 28 1950  
CONS. DIVISION

1028-50

**PLUGGING**  
1950 8 26  
39 5