

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21,959
LEASE NAME Darrol-Irby
WELL NUMBER 1
SPOT LOCATION SW SW NE
SEC. 19 TWP. 8S RGE. 21 (XXXX(W)
COUNTY Graham
Date Well Completed 4/23/84
Plugging Commenced 4/23/84
Plugging Completed 4/23/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR N-B Company, Inc.
P. O. Box 506
ADDRESS Russell, KS 67665

PHONE # (913) 483-5345 OPERATORS LICENSE NO. 6111

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes.

Which KCC/KDHE Joint Office did you notify? District #6.

Is ACO-1 filed? No. If not, is well log attached? Yes.

Producing formation _____ Depth to top _____ bottom _____ T.D. 3659'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	253'	8 5/8"	253'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Mud laden fluid @ 3659'-1650'

20 sks cement @ 1650'

100 sks cement @ 900'

40 sks cement @ 300'

10 sks cement @ 40'

10 sks cement @ Rat Hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750
Address P. O. Box 506
Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well, and I certify that the same are true and
correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Joe K. Branum
(Address) P. O. Box 506
Russell, KS 67665

MAY 01 1984
5-1-84
CONSERVATION DIVISION
WICHITA, KANSAS

Subscribed and sworn to before me this 30th day of April, 1984.
Glenda R. Tiffin
Glenda R. Tiffin, Notary Public

My Commission expires: February 6th, 1988.

15-065-21959-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: N-B Company, Inc.
P. O. Box 506
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Darrol-Irby WELL: #1

LOCATION: SW SW NE
Section 19-8S-21W
Graham County, KS

ROTARY TOTAL DEPTH: 3659'

ELEVATION: 2126 K.B.

COMMENCED: 4/18/84

DATE COMPLETED: 4/23/84

CASING: 8 5/8" @ 253' with 150 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	40'	Shale	3003'
Sand & Shale	257'	Lime & Shale	3244'
Shale	1658'	Lime	3626'
Anhydrite	1720'	Lime & Chert (R.T.D.)	3659'


STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Joe K. Branum

Subscribed and sworn to before me this 30th day of April, 1984.

My Commission Expires: February 6th, 1988.




Glenda R. Tiffin, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

MAY 01 1984 5-1-84

CONSERVATION DIVISION
Wichita, Kansas