


15-065-00251-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 20 Twp. 8 Rge. (E) 21 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/4 NW/4 NE/4  
Lease Owner **Sohio Petroleum Company**  
Lease Name **Brault** Well No. **1**  
Office Address **314 Bitting Building, Wichita 2, Kansas**  
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**  
Date well completed **8/12** 19 **51**  
Application for plugging filed **8/12** 19 **51**  
Application for plugging approved **8/12** 19 **51**  
Plugging commenced **8/12** 19 **51**  
Plugging completed **8/12** 19 **51**  
Reason for abandonment of well or producing formation **Dry**

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well **Mr. Eldon Petty, Hays, Kansas**  
Producing formation Depth to top Bottom Total Depth of Well **3705** Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


Formation	Content	From	To	Size	Put In	Pulled Out
				<b>8-5/8"</b>	<b>1661</b>	<b>Cemented</b>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

**Filled with heavy mud to 160'.  
Set a plug at 160' and filled with  
15 sacks of cement.  
Set second plug at 40' and filled  
with 1/2 sack of hulls and cement to  
bottom of cellar.**

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor **Musgrove Petroleum Corporation**  
Address **407 K.F.H. Building  
Wichita 2, Kansas**



9-18-51

STATE OF **KANSAS**, COUNTY OF **SEDGWICK**, SS.  
**GORDON L. KOELLING** (employee of owner) or (owner) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Gordon L. Koelling*  
**407 K.F.H. Building, Wichita 2, Kansas**  
(Address)

SUBSCRIBED AND SWORN to before me this **15th** day of **August**, 19 **51**

*Nadine J. Irwin*  
Notary Public.

My commission expires **December 5, 1951**

PLUGGING  
FILE SEC-70T 8 R 20  
102 43

CONTRACTOR'S WELL LOG

COMPANY: Sohio Petroleum Company  
 CONTRACTOR: Musgrove Petroleum Corporation  
 FARM: Brault #1  
 LOCATION: NW/4 NW/4 NE/4, Sec. 20-T8S-R21W,  
 Graham County, Kansas  
 COMMENCED: 8/2/51  
 COMPLETED: 8/12/51

0	5	Cellar
5	35	Surface soil and soapstone
35	125	Sand and gravel
125	400	Shale and shells
400	820	Red bed, shale, shells and sand
820	1580	Shale, sand and red bed
1580	1610	Anhydrite
1610	2380	Shale and shells
2380	3170	Lime and shale
3170	3214	Lime
3214	3281	Lime and shale
3281	3505	Lime
3505	3540	Conglomerate
3540	3630	Lime and shale
3630	3705	Arbuckle
	3705	Rotary Total Depth

Set 166' of 8-5/8" surface casing, cemented with 150 sacks.  
 Dry and Abandoned.

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of Brault #1, Sec. 20-T8S-R21W, Graham County, Kansas, as reflected by files of the Musgrove Petroleum Corporation.

9-18-51

MUSGROVE PETROLEUM CORPORATION  
 By Gordon L. Koelling  
 Secretary

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 15th day of August, 1951

Gordon L. Koelling  
 Notary Public

My commission expires: 12/5/51

PLUGGING  
 SEC 20 T8S R21W  
 107 43