


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines Graham County. Sec. 20 Twp. 8S Rge. 21 ~~(E)~~ (W)
Lease Owner Barnett Oil Company
Lease Name Brault Well No. 1
Office Address 411 First National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 13, 1960
Application for plugging filed March 13, 1960
Application for plugging approved March 13, 1960
Plugging commenced March 13, 1960
Plugging completed March 13, 1960
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	--0--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 400' with mud; set plug at 400' with 20 sacks of cement through drill pipe; filled hole to 190' with mud; pushed plug to 190'; put 1/2 sack of hulls on top of plug and 20 sacks cement; filled hole to 40' with mud; pushed plug to 40' and put 1/2 sack of hulls on top and 10 sacks of cement. Plugging completed at 5:00 P.M., March 13, 1960

Bridged rat hole and put 2 sacks of cement on top of bridge.

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1960

CONSERVATION DIVISION
Wichita, Kansas

(Well Log attached)

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Barnett Drilling, Inc.
Address 409 First National Bank Building, Wichita, Kansas

3-21-60

STATE OF Kansas, COUNTY OF Sedgwick, ss.
F. H. Rousey (employee of ~~owner~~ ~~operator~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

F. H. Rousey
411 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1960

My commission expires February 27, 1964.

Mildred F. Willis
Notary Public.



15-065-00631-00-00

BARNETT OIL COMPANY
WELL LOG - BRAULT NO. 1
A/C N/2 NE/4 NE/4 SECTION 20-8S-21W
GRAHAM COUNTY, KANSAS

Date Commenced: 3- 6-60
Date Completed: 3-13-60

<u>From</u>	<u>To</u>	<u>Formation</u>
0	10	Surface Clay
10	50	Sand
50	90	Shale
90	110	Sand
110	610	Shale
610	635	Sand
635	925	Shale
925	1050	Shale and shell
1050	1335	Sand
1335	1614	Shale and shell
1614	1649	Anhydrite
1649	1915	Shale and shells
1915	2150	Shale and lime shell
2150	2380	Shale and shell
2380	3065	Shale and lime
3065	3200	Lime
3200	3345	Lime and shale
3345	3608	Lime
3608	3650	Shale and lime (T.D.) (D. & A.)

Set 8 5/8", 28# used casing
at 200' with 125 sacks of
H.A. 5 cement.

RECEIVED
STATE COMMISSION

MAR 21 1960

CONSERVATION DIVISION

3-21-60