

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-065-21684-00-00

API NUMBER \_\_\_\_\_

LEASE NAME Guillaume

WELL NUMBER 1-34

SPOT LOCATION SE SE SW

SEC. 34 TWP. 8S RGE. 21 (E) or (W)

COUNTY Graham

Date Well Completed 9/29/82

Plugging Commenced 7/25/85

Plugging Completed 7/25/85

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 North Water, Suite 300, Wichita, Kansas 67202

PHONE (316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays

Is ACO-1 filed? Yes If not, is well log attached? No

Producing formation Conglomerate Depth to top 3620 bottom 3668 T.D. 3702'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content  | From | To | Size   | Put in | Pulled out |
|-----------|--|------|----|--------|--------|------------|
|           |  |      |    | 8 5/8" | 231'   | ----       |
|           |  |      |    | 4 1/2" | 3743'  | ----       |
|           | Squeezed @ 1051'-59' and 1138'-70' w/160 sacks |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Connected to 8 5/8" & 4 1/2" annulus. Pumped 100 sacks of 60/40 Pozmix w/8% gel, 3% CC and 1 sack hulls. SIP-125#. Calculated volume of cement in annulus is equivalent to 749'. Connected to 4 1/2" csg. Pumped 100 sacks cement (same mix) w/3 sacks hulls. Followed by 8 sacks gel and 15 sacks cement (same mix). SIP-1000#. Calculated volume pumped down the 4 1/2" csg. is equivalent to 3657'. Approved by Carl Goodrow w/KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company  
Address 250 North Water, Suite 300; Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1985


STATE OF Kansas COUNTY OF Sedgwick, ss.

CONSERVATION DIVISION  
Wichita, Kansas

Pat Canaday, Hill City District, Jr. Engineer (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

8-19-85

(Signature) [Signature]  
(Address) P.O. Box 130, Hill City, KS. 67642



SUBSCRIBED AND SWORN TO before me this 14 day of August, 1985

My Commission expires: 6/24/89

Donna Gerstner  
Notary Public