

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 01 1977
9-1-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -065 -20,952 -00-00 (of this well)

Operator's Full Name A. Scott Ritchie

Complete Address Suite 950-125 N. Market, Wichita, Kansas

Lease Name Kobler "A" Well No. 1

Location NE NE NE Sec. 35 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3980'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil

Address Victoria, Kansas License No.

Operation Completed: Hour 7:30 A Day 31 Month 8 Year 1977

The above well was plugged as follows:

RTD 3980' 8 5/8 csg set 209' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les Messer
Well Plugging Supervisor

DATE 9-1-77

INV. NO. 5765-U