

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

DEC 27 1973

CONSERVATION DIVISION
Wichita, Kansas

12-27-73

15-065-20648-0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Oil Company,

Complete Address Suite 550, 200 West Douglas, Wichita, Kansas.

Lease Name Brumage Well No. 1

Location App: -NE-NE-NW Sec. 36 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3970'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.

Operation Completed: Hour 5:15 PM Day 22 Month 12 Year 1973

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
thru DP from 1125' to 800'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dickel
Well Plugging Supervisor

DATE 12/28/73
INV. NO. 8341-W