

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20655-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 9 - 1974
CONSERVATION DIVISION
Wichita, Kansas
4-9-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Empire Drilling Company,
Complete Address 650 Fourth National Bank Building, Wichita, Kansas.
Lease Name Popp Well No. 1
Location CNE/4 Sec. 36 Twp. 8 Rge. (E) (W) 24
County Graham Total Depth 3900'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,
Address 617 Union Center, Wichita, Ks. License No. _____

Operation Completed: Hour 3:15 AM Day 5 Month 4 Year 1974

The above well was plugged as follows:

221'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dickole
Well Plugging Supervisor

INVOICED

DATE 4/9/74
INV. NO. 8907-W