

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20330-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 4 1970  
CONSERVATION DIVISION  
Wichita, Kansas

64-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name Sanger Well No. 1

Location 140' SNL & 140' EWL of SE/4 Sec. 1 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3980'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 6:00 PM Day 30 Month 5 Year 1970

The above well was plugged as follows:

201'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols  
Well Plugging Supervisor

DATE 6/4/70  
INV. NO. 1994-11