

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-02775-00-00

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Graham

Location: SE SE SW Sec. 5 Twp. 8 Rge. _____ (E) _____ (W) 25

Name of Field: _____ Total Depth: 4027

I have this date completed supervision of plugging of:

Lease Name: Toll Well No. 2

Operator's Full Name: C & G Drg Co

Complete Address: 107 Rule Bldg Wichita, Kansas

Plugging Contractor: Forbes Casing Pulling Co

Address: Great Bend, Kansas License No. 49

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 11AM Day 26 Month 9 Year 61

The above well was plugged as follows:

8 5/8" 207' circulated with cement - 5 1/2" 4027' with 150 sax cement -

PB to 3935' - perf 3911.

Filled with sand to 3900', set 4 sax cement with dump bailer 1/2 pulled 2996'

5 1/2" to 550' - circulated hole with heavy mud through 5 1/2" at 550' (40 sax

Gel mud) - displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180',

displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35' set bridge and

10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Jewel M. Ogden*
Conservation Division Agent

Reviewed: *Harold Hollis*
Field Supervisor

Remarks:

INVOICED

DATE 10/18/61
INV. NO. 3859-W

CONSERVATION DIVISION
WICHITA, KANSAS
10-3-61