

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1969
CONSERVATION DIVISION
Wichita, Kansas

1-13-69

15-065-20196-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Toll Well No. 1

Location App.-CSW-SE Sec. 5 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3800'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 10:00 PM Day 10 Month 1 Year 1969

The Above well was plugged as follows:

213'---8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1280' and displaced 100 Sx. cement thru
DP from 1280' to 955'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichol
Well Plugging Supervisor

DATE 1/14/69
INV. NO. 9184-W