

KANSAS

Form CP-3
Rev. 6-9-67

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-2017-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 - 1968
CONSERVATION DIVISION
Wichita, Kansas

2-7-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 4th National Bank Building, Wichita, Kansas.

Lease Name Madden-Davis Well No. D-1
~~2-1~~

Location NE-NE-SE Sec. 7 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3995'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 4:15 AM Day 5 Month 2 Year 1968

The above well was plugged as follows:

239'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Dakota section from 1000' to 1200'.

Circulated hole with heavy mud. Pull DP to 1225' and displace 100 Sx. cement thru
DP from 1225' to 1000'. Pull DP to 245' and displace 20 Sx. cement thru DP from 245'
to 185'. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 2/7/68
INV. NO. 7213-W