

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-065-02250-0000

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 57-36

LOCATION NW SE SE

SEC. 8 TWP. 8 RGE. 25

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. C-3Lease Madden-Davis

Operator H. Gore Address Wichita, Kans

Field _____ County Graham

Total Depth 3890 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 101' circulated with cement - 5 1/2" at 3885'

with 125 sax cement behind - Baker plugs at 3756' - perforated
at 3750'.

Sand to 3740', set 5 sax cement with dump bailer, pulled

5 1/2", filled with mud to 175', set rock and 20 sax cement,

mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 8 T 8 R 25
BOOK PAGE 57 LINE 36

RECEIVED
DISTRICT CONSERVATION AGENT
WICHITA, KANSAS

Edson Letty
District Conservation Agent

Date 9-2-54

9-7-54