

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20321-0000

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
5-11-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Graham County Well No. 1

Location 110' SW 1/4 & 110' WEL of NE 1/4 Sec. 9 Twp. 8 Rge. (E) (W) 25

County Graham Total Depth 3952'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drilling Company,

Address P. O. Box #261, Great Bend, Kans. License No.       

Operation Completed: Hour 8:00 AM Day 8 Month 5 Year 1970

The above well was plugged as follows:

175'--8 5/8" Surface pipe, cement circulated with 160 Sx.  
Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru  
DP from 1075' to 750'. Pulled DP to 185' and displaced 25 Sx. cement thru DP from  
185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 5/11/70  
INV. NO. 1868-11