

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-00716-00-01

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1964

6-15-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name D. R. Lauck Oil Company, Incorporated,
Complete Address: 301 So. Broadway, Wichita, Kansas.
Lease Name Kobler Well No. 1
Location SE-SE-NW Sec. 24 Twp. 8 Rge. (E) (W)24
County Graham Total Depth 3800'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: Attempted WASHDOWN
Plugging Contractor: Glenn & Smith Pipe Pulling Company,
Address: 204 E. 6th, Ellinwood, Kansas. License No. 396
Operation Completed: Hour 12:00M Day 10 Month 6 Year 1964

The Above well, was plugged as follows:

208'--8 5/8" Surface pipe, cement circulated. 3800' 5 1/2" Production casing cemented to 3050' (Temperature Survey). Well Plugged back to 3777', Top perforations @ 3740'.

Sanded well back to 3730' and set 4 Sx. cement with dump bailer. Pulled 5 1/2" to 600' and circulated heavy gel mud (used 21 Sx. gel). Pulled 5 1/2" to 540' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 200' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 6/15/64

INV. NO. 9302-W