

15-065-02725-00-01

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1974  
2-27-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Incorporated,  
Complete Address 1515 KSB&T Building, Wichita, Kansas.  
Lease Name Holly Unit Well No. 7-2  
Location SE-NE-NE Sec. 31 Twp. 8 Rge. (E) (W) 2h  
County Graham Total Depth 3888'  
Abandoned Oil Well        Gas Well        Input Well X SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Halliburton Services,  
Address Drawer "D", Hill City, Kansas. License No.         
Operation Completed: Hour 12:00 M Day 20 Month 2 Year 1974

The above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3383'--5 1/2" Production casing cemented on bottom with 75 Sx. Open hole completion.  
Junk in hole @ 2607'.  
Well flowed salt water thru 5 1/2" casing when it was opened, squeezed 5 1/2" with 35 Sx.  
cement followed by plug to top of junk @ 2607'. Pulled 5 1/2" casing (1259)' and  
squeezed well initially with 5 sacks hulls and 18 sacks gel and followed with 110 Cu.  
Ft. cement from 1125' to 800' then 13 sacks gel from 800' to 280' and followed with  
30 Cu. Ft. cement from 280' to 200' then 4 sacks gel from 200' to 40' and finally 10  
Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-400#, Final  
shut-in pressure-150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/27/74

INV. NO. 8654-W

Signed: W. L. Nichols  
Well Plugging Supervisor