

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
AUG 7 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Holley Unit Well No. Tract #6, Well #1

Location NW-NW-NW Sec. 31 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 4041'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:45 PM Day 3 Month 8 Year 1973

The above well was plugged as follows:

315'--10 3/4" Surface casing, cement circulated with 200 Sx. (9" Hole).
4040'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool @ 2212' with
140 Bbl Black Magic circulated to surface. Well plugged back to 3987' with top per-
forations from 3958' to 3980'.

Sanded well back to 3940' and set 6 Sx. cement with dump bailer. Pulled 7" casing
(1090') and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed
with 150 Cu. Ft. cement from 1250' to 900' then 20 sacks gel from 900' to 350' and
followed with 55 Cu. Ft. cement from 350' to 250' then 10 sacks gel from 250' to 25'
and finally 15 Cu. Ft. cement from 25' to bottom of cellar. Max. Pump-in press.-350#.
FSIP-100#. (Mudding and cementing by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

Signed: W. G. Nichols
Well Plugging Supervisor

INVOICED

DATE 8/8/73
INV. NO. 7739-u