

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 25 1973  
10-25-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 KSB&T Building, Wichita, Kansas.

Lease Name Holley Unit Well No. 6-6

Location SE-NW-SW Sec. 31 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 4014'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address P. O. Box #364, Great Bend, Kansas License No. 399

Operation Completed: Hour 12:00 M Day 17 Month 10 Year 1973

The above well was plugged as follows:

313'--10 3/4" Surface casing, cement circulated with 210 Sx.  
3996'--7" OD Production casing cemented on bottom with 100 Sx. Well plugged back to  
3968'. Top perforations from 3936' to 3961'.

Sanded well back to 3900' and set 7 Sx. cement with dump bailer. Pulled 6" casing  
(2830') and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed  
with 150 Cu. Ft. cement from 1250' to 900' then 20 sacks gel from 900' to 350' and  
followed with 55 Cu. Ft. cement from 350' to 250' then 10 sacks gel from 250' to 25'  
and finally 15 Cu. Ft. cement from 25' to bottom of cellar. Maximum Pump-in pressure-  
-200#. Final Shut-in pressure-150#. (Mudding and cementing operations by Halliburton).

I **INVOLICED** hereby certify that the above well was plugged as herein stated.

DATE 10/25/73

INV. NO. 8064-10

Signed: H. L. Driehk  
Well Plugging Supervisor