

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1973

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,

Complete Address 1515 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Holley Unit Well No. 6-7

Location NW-SE-NW Sec. 31 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 4010'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address P. O. Box #364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4:00 PM Day 16 Month 10 Year 1973

The above well was plugged as follows:

328'--10 3/4" Surface casing, cement circulated with 210 Sx.

4003'--7" OD Production casing cemented on bottom with 100 Sx. Well plugged back to 3997'. Top perforations from 3940' to 3944'.

Sanded well back to 3925' and set 7 Sx. cement with dump bailer. Pulled 7" casing

(2705') and squeeze well initially with 7 sacks hulls and 20 sacks gel and followed

with 150 Cu. Ft. cement from 1250' to 900' then 20 sacks gel from 900' to 350' and

followed with 55 Cu. Ft. cement from 350' to 250' then 10 sacks gel from 250' to 25'

and finally 15 Cu. Ft. cement from 25' to bottom of cellar. Maximum Pump-in pressure-

-250#. Final Shut-in pressure-75#. (Mudding and cementing by Halliburton).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/23/73

INV. NO. 8049-W

Signed: W. L. Duchak  
Well Plugging Supervisor