

15-065-02736-00-01

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,  
Complete Address 1515 KSB&T Building, Wichita, Kansas.  
Lease Name Holly Unit Well No. 6-11  
Location NW-SE-SW Sec. 31 Twp. 8 Rge. (E) (W) 2h  
County Graham Total Depth 4003'  
Abandoned Oil Well        Gas Well        Input Well X SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Halliburton Services,  
Address Drawer "D", Hill City, Kansas. License No.         
Operation Completed: Hour 11:00 AM Day 20 Month 2 Year 1974

The above well was plugged as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx.  
4000'--7" OD Production casing cemented on bottom with 100 Sx. 7" casing has been  
squeezed @ 3958'. Top of perforations @ 3893'.  
Sanded well back to 3850' and set 6 Sx. cement with dump bailer. Pulled 7" casing  
(1200') and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed  
with 83 Sx. Halliburton Lite cement from 1250' to 900' then 20 sacks gel from 900'  
to 350' and followed with 27 Sx. cement from 350' to 250' then 10 sacks gel from 250'  
to 25' and finally 10 Sx. cement from 25' to bottom of cellar. Maximum pump-in press-  
ure-250#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2/27/74  
INV. NO. 8653-10