

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Petroleum Management, Incorporated,  
Complete Address 1515 KSB&T Building, Wichita, Kansas.  
Lease Name Holly Unit Well No. 6-13  
Location SE-NE-SW Sec. 31 Twp. 8 Rge. (E) (W) 24  
County Graham Total Depth 3988'  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Halliburton Services,  
Address Drawer #D", Hill City, Kansas. License No.         
Operation Completed: Hour 1:00 PM Day 19 Month 2 Year 1974

The above well was plugged as follows:

320'--10 3/4" Surface casing, cement circulated with 210 Sx.  
3985'--7" OD Production casing, cemented on bottom with 100 Sx. No plug-back indicated. Top perforations from 3964' to 3968'.  
Sanded well back to 3950' and set 6 Sx. cement with dump bailer. Pulled 7" casing (1175') and squeezed well initially with 7 sacks hulls and 20 sacks gel and followed with 83 Sx. Halliburton Lite Cement from 1250' to 900' then 20 sacks gel from 900' to 350' and followed with 27 Sx. cement from 350' to 250' then 10 sacks gel from 250' to 25' and finally 10 Sx. cement from 25' to cellar. Max. Pressure-600#, PSIP-450#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/27/74  
INV. NO. 8639-W

Signed: W. L. Dickel  
Well Plugging Supervisor