

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED
FEB 18 1982
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-065-21,584-00-50

200 Colorado Derby Bldg
Wichita, KS 67202

Operator's Full Name Oil Capital Corp.
Complete Address 411 Farmers & Bankers Bldg; Wichita, KS, 67202
Lease Name Toll Well No. 1
Location NW-SE-SW Sec. 15 Twp. 8 Rge. 25 (East) (West)
County Graham Total Depth 3890
Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated
Plugging Contractor Abercrombie Drlg. Co. (Rig 4)
Address 801 Union Centes; Wichita, Kansas License No.
Operation Completed: Hour: 2:00 A. Day: 15 Month: 2 Year: 19 82
Plugging Operations attended by Agent?: All Part None X

The above well was plugged as follows:

Set 8 5/8" @ 207' w/ 325 sk 2% gel 3% O.A. - (Sun)
Ordered 130 sk 5% pozmix 4% gel - 3% O.A. + 8 5/8" plug
Spotted 70 sk @ 1100' - Spotted 40 sk @ 200' - Spotted
10 sk on solid bridge of kulls and plug @ 40' to 0' -
Spotted 10 sk. in rat hole - Circulate heavy mud
between all plugs.

(Cont. by Sun)

Amount of Surface Casing: 207'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Out on another job - Big Springs - Dancer #1 4-8-17th

Signed: Dennis L. Hamel
Conservation Division Agent

2-25-82
9500-0

2/18/82

RECEIVED
FEB 18 1982
CONSERVATION DIVISION
Wichita, Kansas