

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-065-21, 7021-00-00

NE-SW-SW, Sec. 24, T 9 S, R 22 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name HERN Well # 1

Operator: CHIEF DRILLING Co.
Name & Address 905 CENTRY PLAZA.
WICHITA, KANS.
67202

County GRAHAM

Well Total Depth 3906 feet

Conductor Pipe: Size — feet —

Surface Casing: Size 8 5/8 feet 3906

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor CHIEF DRILLING Co. License Number 279

Address 905 CENTRY PLAZA. WICHITA, KANS. 67202

Company to plug at: Hour: 8:00 AM Day: 15th Month: OCT. Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO HAROLD DINNELL

(company name) CHIEF DRILLING Co. (phone) 316-262-2791

were: 8 5/8" - 210 FT SP. CUC. w/150st COMMON-2% GEL-3% CA-CL. (ALLIED)

ORDER - 200st 50st Formix 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3720 FT w/20st CMT, 2nd PLUG @ 1860 FT w/20st CMT,

3rd PLUG @ 1080 FT w/100st CMT. 4th PLUG @ 240 FT w/40st CMT.

5th PLUG. SOLID BRIDGE HULL'S - PLUG @ 40 FT w/0st w/10st CMT. Signed Mason Schmidt

10st IN RAT HOLE. (CIRCULATE) (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:00 PM Day: 15th Month: OCT Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" 210 FT SP. CUC. BY ALLIED CMT.

ORDERED 200st 50st Formix 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 3720 FT w/20st CMT. → 2nd PLUG @ 1860 FT w/20st CMT.

3rd PLUG @ 1080 FT w/100st CMT. 4th PLUG @ 240 FT w/40st CMT.

5th PLUG. SOLID BRIDGE HULL'S - PLUG @ 40 FT w/0st w/10st CMT. 10st IN RAT HOLE

(CIRCULATE)

Remarks: CEMENTED BY ALLIED CMT.

RECEIVED
STATE CORPORATION COMMISSION
10/26/82
OCT 26 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

INVOICED
DATE 11-15-82
INV. NO. 1543-W

Signed Mason Schmidt
(TECHNICIAN)