

4-042048

15-065-01532-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 1-3-58

SE SE NE /4 SEC. 24, 09 S, 22 W  
2970 feet from S section line  
330 feet from E Section line

Operator license# 5030

Lease: Mills Well # 1

Operator: Vess Oil Corporation

County: Graham 126.33

Address: 8100 E. 22th Street North  
Bldg #300  
Wichita, Kansas 67226

Well total depth 3887 feet  
Conductor Pipe: inch @ feet  
Surface Pipe: 8 5/8 Inch 202 Feet  
W/circ.sxs cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 4 Month: April Year: 2000

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: -

Were: Ordered 250 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 900# hulls.  
5 1/2" casing set at 3886' w/175 sxs cement. Perf at 3425' - 3650'.  
D.V. anhy. At 1854' w/540 sxs. Squeeze at 1558' w/125 sxs.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 12:00 P.M., Day 4, Month: April, Year: 2000

Actual plugging report: Pumped down 5 1/2" casing. 75 sxs cement with 400# hulls, followed with 14 sxs gel followed with 150 sxs cement with 500# hulls. Max. P.S.I. 400# S.I.P. 100#. Squeezed 8 5/8" S.P. with 500# P.S.I. Job Complete.

RECEIVED  
STATE CORPORATION COMMISSION  
5/3/00  
MAY 3 2000

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING CASING Elevation: G.I.

I did [ X ] / did not [ ] observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED  
DATE 5/5/00  
INV. NO. 061673

(R)