

6 020433

12-18-87 15-065-03412-0000  
API NUMBER 15- Approx 1952

CORPORATION COMMISSION  
REGISTRATION DIVISION - PLUGGING SECTION NW SE NE/4, SEC. 26, T 9 S, R 22 W/E  
COLORADO DERBY BUILDING  
TA, KANSAS 67202

To: STATE CONSERVATION COMMISSION  
Operator License # 5465

Operator: John B. Collins  
Name & Address: 2911 Canterbury  
Hays, Kansas 67601  
913-628-1046

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor John B. Collins License Number 5465  
Address \_\_\_\_\_

Company to plug at: Hour: 9:00 Day: 1 Month: Dec. Year: 19 87

Plugging proposal received from Vernon Chard  
(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Order 200 sks 50/50 Poz 6% Gel 3% Ca Cl 1 sk Flocele and 8 5/8" plug.  
Spot with drill pipe with no less than 36 vis. mud between all plugs with good circulation and no fluid loss.  
Order 200 sks Econolite Common and 5 sks Hulls.

Plugging Proposal Received by Gilbert Balthazor  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 11:30AM Day: 18 Month: Dec. Year: 19 87

ACTUAL PLUGGING REPORT  
Bottom plug. Squeezed bridge plug at 3000'.  
5 5/8 w/holes 1577' and 1607' squeeze to 1200'  
" holes 1200' squeeze w/200 sks CWC  
Pumped down 5 5/8 15 sks Econolite  
" " " 160 sks w/Hulls.

12/29/87  
DEC 2 1987  
CONSERVATION DIVISION  
Topeka, Kansas

Remarks: Max pressure 700 lbs and shut in pressure 300 lbs.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-6-88  
INV. NO. 19361  
12-18

FEB 24 1988

Signed Gilbert Balthazor  
(TECHNICIAN)  
Gilbert Balthazor